

: Registration form for the cold room / cold chain :

GCMMF invites suppliers in turnkey project work for walk in cold room and have after sales service network across country. Interested supplier, please visit our website www.amul.com-B2B (Supplier Data on Firm) and send form duly filled in all respect to HOD(Purchase), Gujarat Coop.Milk Marketing Federation Ltd,Amul Dairy Road, Anand . The detail requirement of walk in cold rooms are as follows :

Branch	Description
Turn key requirement Tentative planning for Vizag	5000 CFT internal volumetric capacity Wet product cold room (New) with one 20000 BTUH capacity new unit . Supplier has to provide walk in cold room rates and miscellaneous work estimate as well as technical data of the cold room . The old Refrigeration System to be utilize in this cold room which are laying with our Vizag plant (Refrig Units detail : 10000 BTUH* 3 nos BSL purchased in yr.2014 only).
Turnkey requirement Tentative planning for Cuttack	<p>Frozen Product storage of product at 2 Deg.cent:</p> <p>We have own 5000 CFT old frozen cold room carrier make. Age wise this cold room is 10 years old.</p> <p>Buyback offer : Supplier shall offer buyback for this cold room installed with 3 nos. 3 HPLT (10000 BTUH old Refrig. units and all PUF panels) .</p> <p>Not to be considered for Buyback offer</p> <p>Recently , new installation of 1 No. 3 HPLT (10000 BTUH) is not to be included in buyback. All servo stabils. are not to be included for buyback offer.</p>
Turnkey requirement Tentative planning for Silchar	<p>Wet Product storage of product at 0 Deg.cent: 15000 CFT new cold room requirement for both locations.</p>
Turnkey requirement Tentative planning for Indore	<p>Wet Product storage of product at 0 Deg.cent: 15000 CFT new cold room requirement for both locations.</p>

Wet products :The offer to be provided for 55 to 60 Deg.cent condensor temp and -5 deg.cent of evaporator temperature. **Frozen products :** The offer to be provided for 55 to 60 Deg cent of condensor temp and - 25 deg.cent for evaporator temperature.

The highlights of the requirement is as follows:

The cold room to be provided with commissioning work with five years of additional warranty period covering all spare parts and preventive maintenance four per annum basis, servo control stabilizers of 30 % higher capacity for each machines , kota stone flooring work, guiding bar, brick support wall , complete electrification and electrical panel, supply from main tap etc .The iron channel for ceiling support and hatch channel work cable etc in the scope of supplier .