

AFD: CIVIL: INQ: 20190901

September 04, 2019

To,

Sub: - Inquiry for civil work for Endura Tiles flooring and misc. work at IDMC CIP room at AmulFed Dairy, Gandhinagar.

We invite your most competitive offer, quoting your lowest rate and shortest execution period for item mentioned as under. Your offer must be sent in sealed reply envelope attached herewith by registered post/courier or by person. **Mention, "Civil work for Endura Tiles flooring and misc. work at IDMC CIP room at AmulFed Dairy, Gandhinagar."** on top of the offer reply envelope.

Detailed Technical Specification & Schedule of Quantities as per Enclosed Annexure: - I

Last date of receipt of Quotation: 11th September 2019.

➤ **General Terms & Conditions.**

1. Contractor has to quote rates considering work is to be carried out at AmulFed Dairy, Gandhinagar.
2. Your rates should be including of all material cost, labour cost, octroi, loading, unloading at AmulFed Dairy.
3. The Contractor will have to bring his own tools, tackles, ladders, accessories, scaffolding etc.
4. Specify Tax Condition. GST will be applicable or not. If tax condition is not specified your rates shall be considered as inclusive of all taxes.
5. **It is advisable to visit the site before quoting your rates.**
6. If work is to be carried out in emergency basis or during Shutdown period, contractor should carry out work on emergency basis, night work shall be permitted under such Intervention to meet production schedule.
7. Payment terms: 30 days after submission of bill based on JMS / JMR.
8. Quantity indicated here is estimated; it may vary on either side however payment shall be made as per the actual work executed at site based on JMS / JMR.
9. To the extent possible extra item shall be avoided. If however is necessary done as per site Condition & is not envisaged in the current SOR we shall fix the rate base on competitive Offers from the market which shall be binding to the contractor. Contractor should inform

well in advance about the requirement of the extra item to us to get enough time to collect Comparative offers.

10. All the legal/administrative records like muster roll, salary register, labour license, PF, ESI etc. to be maintained & submitted as and when required and contractor is responsible for labour laws and rules/regulations etc.
11. Cleaning of site must be required after day-to-day work.
12. Your workmen should wear the identity card of your company while executing jobs at AFD, Gandhinagar.
13. In case, any of your workmen get injured due to Accident, while working within premises of AFD, or any damage to our equipment or property has taken place due to your workmen, you will repay the damages/losses.
14. We are ISO 9001:2004 QMS (Quality Management System), ISO 14001:2004 (Environmental Management System) ISO 22000:2005 FSS (Food & Safety System) certified unit. We expect you to follow eco-friendly process in your Company such as waste minimization, reduction in air pollution, waster pollution and soil Contamination etc.
15. Chewing pan masala, tobacco & smoking is strictly prohibited in AFD premises and if any person is catch then penalty would be Rs. 5000/- each.
16. You shall be working in running factory and ensure that the day to day operations of the factory are not hampered in any way due to your activities. Any damages occurred by you shall be recovered. Proper barricading of the work area should be done to prevent dust dirt etc. in the environment.
17. Water and Electricity will be provided by AFD free of cost.
18. Safety is the utmost priority inside the premises & Contractor must ensure your team to follows all the safety norms (like use of PPE Personal Protective Equipments, fall protection, secured & safe staging, scaffolding etc.) A safety hand book shall be provided for ready reference if required. If any person not following the safety rules and regulations penalty would be Rs. 1000/- from the Bill.
19. Contractor shall indemnify AFD from any kind of losses due to the activities of the contractor.

AmulFed Dairy shall not accept the offer, received later than the date mentioned above.

Yours faithfully,

For, AmulFed Dairy, Gandhinagar.

Annexure - I

Technical Specification and Scope of work for civil work for Endura Tile flooring and miscellaneous work at IDMC CIP room at AFDG.

Sr. No.	Description	UOM	Qty.	Rate	Amount Rs.
1	Providing & fixing 20mm thick approved make Endura tiles like Johanson / Pavit in cement mortar 1 : 4 (1 cement : 4 coarse sand) 30mm thick bedding including filling the epoxy joints 8mm to 10mm wide all around and filling the same with epoxy resin and hardener of approved make like Araldite / Chemiprotect, line level, necessary curing, cleaning after laying etc. complete as directed.	Sqmt	90.00		
2	Removing any type of existing flooring & dado including removing debries outside the premises as & where directed.	Sqmt	105.00		
3	Dismantling R.C.C work including cutting reinforcement & removing debries within / outside the premises as & where directed.	Cmt	15.00		
4	Excavation in all kinds of soils upto 1.50mt depth for all type of foundations, trenches, roads, surface levelling etc. dressing sides and bottom of the excavated area battering or forming benches, pumping & bailing out of water, shoring and strutting sides of excavation, refilling including ramming watering, consolidating etc., including disposing of surplus earth upto 1500mts within/ outside the Mother Dairy site as directed.	Cmt	11.00		
5	Providing & laying Cement Concrete 1 : 4 : 8 mix (1 cement : 4 coarse sand : 8 graded hard stone aggregate 40 mm nominal size) in foundations and under floors including mixing, compacting, curing etc. complete as directed.	Cmt	8.00		
6	Providing and laying machine mixed & machine vibrated reinforced cement concrete mix of M-25 grade for foundations, plinth, Columns beams, slabs, retaining walls, cantilever slabs & tie beams, lintels, chajjas, pardis, railings, rib beams, staircase slabs and landings (conventional folded & stringer), walls with or without pilasters / butt resses, fins, facias, gutters, waffles, pargola, over head & U. G. water tank, road kerbing etc. at all level below ground and up to 6.00 Mtrs. above ground as per deisgn given by engineer incharge etc. complete as directed.	Cmt	15.00		
7	Providing and fabricating approved make TMT reinforcement steel for RCC work including bending, binding and placing in position and tying the system with soft drawn annealed binding wire of diameter not less than 1.00 mm with 2 strands etc. complete as directed.	Kg.	1100.00		
8	Providing form work using steel plates / ply woods including centering and shuttering, strutting and propping etc complete for all type of RCC work at all levels below ground and up to 7.00 mtrs. above plinth level as per design & drawing given by architect / enigneer including subsequent removal complete as directed.	Sqmt	70.00		
9	Providing & laying brick masonry using bricks having minimum compressive strength 35 kg / cm ² and fixed in to the cement mortar 1 : 5 (1 cement : 5 coarse sand) in foundations and upto all levels including racking of joints, scaffolding, curing etc. complete as directed.	Cmt	1.00		
10	Providing 20 to 25 mm thick water proof cement plaster in double coat on any surface at all heights, finish even and smooth in CM 1 : 4 including providing and mixing water proofing material such as pidilite or equivalent as approved by engineer in cement mortar as proportion recommended by manufacture.	Sqmt	16.00		

Annexure - I

Technical Specification and Scope of work for civil work for Endura Tile flooring and miscellaneous work at IDMC CIP room at AFDG.

Sr. No.	Description	UOM	Qty.	Rate	Amount Rs.
11	Providing and applying 20 mm thick sand face cement plaster in two coat at all heights with first coat of 12mm with cement mortar 1:4 (1 part cement : 4 part of sand) and second coat of 1:3, rough finish with using spronge, on all types of concrete/brick surfaces macking grooves, forming pattas and drip moulds as per the detail, including scaffolding, curring etc. complete as directed.	Sqmt	10.00		
12	Providing & laying single coat 12 mm thick plaster in cement mortar 1 : 4 (1 cement : 4 fine sand) with cement mala finish (finish with steek trover) at all levels including necessary scaffolding, curing, making grooves, forming pattas and drip moulds etc. complete in all respect as directed.	Sqmt	10.00		
13	Providing and fixing avarage 20-25mm thich Redmandana stone in epoxy mortaras under. Applying of two coats of Acid Alkali preventive primer at bottom, fixing on average 37mm thick cement mortar bedding (1:4) with Acid proof powder, keeping the joints 8mm to 10mm wide all around and filling the same with epoxy resin and hardener of approved make like Araldite / Chemiprotec including machine polishing etc. complete as directed.	Sqmt	6.00		
14	Providing & filling Acid Alkali proof Epoxy joint of redmandana stone by using epoxy resin of approved make Araldite / Chemiprotec including removing of decayed joint materials, surface prepration, opening & cleaning of the joints before re-filling the new apoxy mortar etc. complete as directed.	Rmt	100.00		
15	Providing and laying in position ceramic/Glazed tiles for flooring, skirting and wall dado of approved make and colour for first quality of any size as per design fixing in cement slurry over 12-15mm thick cement mortar bedding (1 : 4) and laid to proper slope and level. Joints shall be filled with specified colour pigment to match the shade of tiles including curing and cleaning with mild auxalic acid etc. complete as directed. (Basic rate Rs. 400/- per sqmt) Note :- Rate should be inclusive of backing coat of plaster.	Sqmt	8.00		
16	Making and finishing cut-outs in bricks work upto thickness of 400mm for any height and following sizes including necessary dismentaling, debries removing, finishing with plaster to match with existing surface in proper line & level, scaffolding, grouting of sleeves etc. complete as directed.				
a.	size: up to 300mm	Nos.	2.00		
b.	size: 300mm to 600mm	Nos.	2.00		
17	Supply of skilled mason	Nos	2.00		
18	Supply of un skilled Labour	Nos	5.00		
19	Tractor Trips	Nos	2.00		
	Total Amount	Rs.			
	GST @ 18%	Rs.			
	Amount with GST	Rs.			