

AFD: CIVIL: INQ: 20200201

February 11, 2020

To,

Sub: - Inquiry for civil work for PU flooring, Coving and Joint filling at Butter Plant at AmulFed Dairy, Gandhinagar.

We invite your most competitive offer, quoting your lowest rate and shortest execution period for item mentioned as under. Your offer must be sent in sealed reply envelope attached herewith by registered post/courier or by person. **Mention, "Civil work for PU flooring, Coving and Joint filling at Butter Plant at AmulFed Dairy, Gandhinagar."** on top of the offer reply envelope.

Detailed Technical Specification & Schedule of Quantities as per Enclosed Annexure: - I

Last date of receipt of Quotation: 22nd February 2020.

➤ **General Terms & Conditions.**

1. Contractor has to quote rates considering work is to be carried out at AmulFed Dairy, Gandhinagar.
2. Your rates should be including of all material cost, labour cost, octroi, loading, unloading at AmulFed Dairy.
3. The Contractor will have to bring his own tools, tackles, ladders, accessories, scaffolding etc.
4. Specify Tax Condition. GST will be applicable or not. If tax condition is not specified your rates shall be considered as inclusive of all taxes.
5. **It is advisable to visit the site before quoting your rates.**
6. If work is to be carried out in emergency basis or during Shutdown period, contractor should carry out work on emergency basis, night work shall be permitted under such Intervention to meet production schedule.
7. Payment terms: 30 days after submission of bill based on JMS / JMR.
8. Quantity indicated here is estimated; it may vary on either side however payment shall be made as per the actual work executed at site based on JMS / JMR.
9. To the extent possible extra item shall be avoided. If however is necessary done as per site Condition & is not envisaged in the current SOR we shall fix the rate base on competitive Offers from the market which shall be binding to the contractor. Contractor should inform

well in advance about the requirement of the extra item to us to get enough time to collect Comparative offers.

10. All the legal/administrative records like muster roll, salary register, labour license, PF, ESI etc. to be maintained & submitted as and when required and contractor is responsible for labour laws and rules/regulations etc.
11. Cleaning of site must be required after day-to-day work.
12. Your workmen should wear the identity card of your company while executing jobs at AFD, Gandhinagar.
13. In case, any of your workmen get injured due to Accident, while working within premises of AFD, or any damage to our equipment or property has taken place due to your workmen, you will repay the damages/losses.
14. We are ISO 9001:2004 QMS (Quality Management System), ISO 14001:2004 (Environmental Management System) ISO 22000:2005 FSS (Food & Safety System) certified unit. We expect you to follow eco-friendly process in your Company such as waste minimization, reduction in air pollution, waster pollution and soil Contamination etc.
15. Chewing pan masala, tobacco & smoking is strictly prohibited in AFD premises and if any person is catch then penalty would be Rs. 5000/- each.
16. You shall be working in running factory and ensure that the day to day operations of the factory are not hampered in any way due to your activities. Any damages occurred by you shall be recovered. Proper barricading of the work area should be done to prevent dust dirt etc. in the environment.
17. Water and Electricity will be provided by AFD free of cost.
18. Safety is the utmost priority inside the premises & Contractor must ensure your team to follows all the safety norms (like use of PPE Personal Protective Equipments, fall protection, secured & safe staging, scaffolding etc.) A safety hand book shall be provided for ready reference if required. If any person not following the safety rules and regulations penalty would be Rs. 1000/- from the Bill.
19. Contractor shall indemnify AFD from any kind of losses due to the activities of the contractor.
20. All jobs executed must remain under **one year defect liability period** pertaining to defects due to bad workmanship, use of sub-standard materials, improper methods of application etc and must be attended free of charge during this period.
21. **Security deposit 10% of the total cost of the project**, which will be submitting in the form of bank guarantee at time of acceptance of order and will be released after 15 month after completion date.

AmulFed Dairy shall not accept the offer, received later than the date mentioned above.

Yours faithfully,

For, AmulFed Dairy, Gandhinagar.

Annexure : I

Technical Specification and Scope of work for Civil work for PU Flooring, Coving and Joint Filling work at Butter Plant at AFDG.

Sr No	Item Description	UOM	Quantity	Rate	Amount
1	6 mm Thick PU flooring	SQ.Mtr	1400.00		
	Scarifying existing surface , creating groves and vacuum cleaning the same . Remove lose area if any and Patching the same, Then laying scratch coat and allowed to set , followed by PU top coating in approved shade to get a monolithic finish and total thickness of the floor is 6 mm Thick.				
2	Existing Joint filling with PU Material	RMT	5000.00		
	Cleaning all the joints and filling with PU material (Joint size as per the Site condition)				
3	Epoxy Coving	RMT	500.00		
	It is constructed at 90 Degree Junction - Wall-wall , Wall -Floor & Wall -Ceiling Junction , And it is constructed with solvent less epoxy with High abrasion resistant aggregates , Topping with PU coating				
	Approved Make : Flowcrete , Ucrete				
	Total Amount	Rs.			
	GST	Rs.			
	Total Amount with GST	Rs.			