

AFD: CIVIL: INQ: 20240301

2<sup>nd</sup> March, 2024

To,

Sub: - Inquiry for Painting work of various chimneys and 60 TPD Powder Plant at AFDG.

Dear Sir,

We invite your most competitive offer, quoting your lowest rate and shortest execution period for item mentioned as under. Your duly signed offer must be sent in sealed reply envelope attached here with super subscribed with QUOTATION for "Painting work of various chimneys and 60 TPD Powder Plant at AFDG."

Detailed Technical Specification & Schedule of Quantities as per Enclosed Annexure: - I

Last date of receipt of Quotation: 13th March 2024.

## General Terms & Conditions.

- 1. Your rates should be including of all material cost, labour cost, octroi, loading, unloading at AFD Gandhinagar.
- 2. The contractor will have bring his own tools, tackles, accessories and Special Scaffolding to reach 35 mtr. Height etc.
- 3. Specify Tax Condition. GST will be applicable or not. If tax condition is not specified your rates shall be considered as inclusive of all taxes.
- 4. It is advisable to visit the site before quoting your rates.
- 5. Payment terms: 30 days after submission of bill.
- 6. Quantity indicated here is estimated; it may vary on either side.
- 7. All the legal/administrative records like muster roll, salary register, labour license, PF, ESI etc. to be maintained & submitted as and when required and contractor is responsible for labour laws and rules/regulations etc.
- 8. Cleaning of site must be required after day-to-day work.
- 9. Your workmen should wear the identity card of your company while executing jobs at AFD, Gandhinagar.
- 10. In case, any of your workmen get injured due to Accident, while working within premises of AFD, or any damage to our equipment or property has taken place due to your workmen, you will repay the damages/losses.

M.c. Mella

11. We are ISO 9001:2004 QMS (Quality Management System), ISO 14001:2004 (Environmental Management System) ISO 22000:2005 FSS (Food & Safety System) certified unit. We expect you to follow eco-friendly process in your Company such as waste minimization, reduction in air pollution, water pollution and soil Contamination etc.

12. Chewing pan masala, tobacco & smoking is strictly prohibited in AFD premises and if any person is catch then penalty would be Rs. 5000/- each.

- 13. You shall be working in running factory and ensure that the day to day operations of the factory are not hampered in any way due to your activities. Any damages occurred by you shall be recovered. Proper barricading of the work area should be done to prevent dust dirt etc. in the environment.
- 14. Water and Electricity will be provided by AFD free of cost.
- 15. Safety is the utmost priority inside the premises & Contractor must ensure your team to follows all the safety norms (like use of PPE Personal Protective Equipments, fall protection, secured & safe staging, scaffolding etc.) A safety hand book shall be provided for ready reference if required. If any person not following the safety rules and regulations penalty would be Rs. 1000/- from the Bill.
- 16. Contractor shall indemnify AFD from any kind of losses due to the activities of the contractor.
- 17. Security deposit would be 2.5% of the Project cost and Retention money would be 2.5% of the Project cost. Both are in Bank Guarantee form and which will be release after 15 month of Project completion.
- 18. Total Completion Time for the said work 120 days from site hand over (Phase manner).

AmulFed Dairy shall not accept the offer, received later than the date mentioned above.

Yours faithfully,

M.c. menta

For, AmulFed Dairy, Gandhinagar.

Date: 02/03/2024

## Annexure: I

Technical Specification and Scope of work for Painting work of various chimneys and 60 TPD Powder Plant at AFDG.

Item No.	Item Description	UOM	Qty.	Rate	Amount
A	Painting and white washing work for 60 TPD Powder Plant.				
1	Providing and applying white/colour washing with lime on new/old work at all height, with two or more coats on wall, ceiling, beam, column, AC sheets etc. including adding of glue of" Pidilite co." or equivalent, indigo (Blue). Including surface preparation like scraping & rubbing the old white washed surface properly, scraping after laying the plastic sheet, filling the uneven surface by plaster of Paris & white cement to make the surface even, final coat shall be applied by brush only, plastic sheet, all tools & tackles, ladders, scaffolding, wire rope etc. All the application work to be done by following the procedure specified by the manufacturer and explains practically during the execution of the work etc. complete as directed by engineer in charge.	Sqmt	20000.00		
2	Providing and applying exterior grade acrylic paint on walls, ceilings, beams etc. at all heights with two or more coats of Approved make & shade (e. g. Berger, Nerolac, Asian etc.) Including surface preparation like scraping & rubbing the old loose paint, laying the plastic sheet, filling the patches by plaster of Paris & white cement to make the surface even, all tools & tackles, ladders, wire rope etc. All the application work to be done by following the procedure specified by the manufacturer and explains practically during the execution of the work etc. complete as directed by engineer in charge.	Sqmt	7000.00		
3	Providing and applying of approved shade & make like Asian/Berger/Nerolac Plastic emulsion paint at all height on plastered and white washed surface, with two or more coats of paint applied by brush and final coat applied by roller. Including Providing of "BIRLA / JK white cement based putty in two coats for preparation of surface for painting like cleaning, rubbing, scraping after laying the plastic sheet, all tools & tackles, ladders, wire rope etc. All the application work to be done by following the procedure specified by the manufacturer and explains practically during the execution of the work etc. complete as directed.	Sqmt	1000.00		
4	Providing and applying of approved shade & make like Asian/Berger/Nerolac synthetic enamel paints at all heights on new / old work, on wooden surface, Plaster surface, MS structures, Pipes, MS supports, with two or more coats of paint applied by brush including the preparation of surface for painting, providing & applying wood primer/Red oxide, putty wherever required in two coats for preparation of surface for painting like cleaning, rubbing, scraping after laying the plastic sheet, scafolding, all tools & tackles, ladders, wire rope etc. complete as directed. (measurement of element periphery less then 300 mm consider is 300 mm, unit of measurement is Sqmt only)	Sqmt	2500.00		

Annexure: I

Technical Specification and Scope of work for Painting work of various chimneys and 60 TPD Powder Plant at AFDG.

Item					
No.	Item Description	UOM	Qty.	Rate	Amount
5	Providing and applying melamine polish of approved make like "Teralac, Asian or ICI on furniture including all necessary surface preparation, like rubbing the furniture surface till surface become smooth, applying powder to match the required shade (natural), applying melamine layer, rubbing the polished surface for smoothness & even layer of polishing, filling the patch by putty, scraping the same, again applying the powder layer & polish layer then applying two coats of melamine layer by machine etc. complete as directed.	Sqft.	100.00		
6	Do as above item No-12 but Rft.	Rft.	200.00		
-,	Total Amount for A	Rs.		*	
	GST @ 18%	Rs.			
	Total Amount with GST for A	Rs.			
	9				19
В	Painting work for Boiler, CPP & Powder Plant's chimneys				
1	Providing and applying two or more coats with brush of special chimney paint of approved make like ("Aluminium chimney paint of BERGER" or Tuffkote – Lusterotherm HT 400 silicone aluminium paint of SHALIMAR) on chimney. Including scrap of the existing paint, rust removing and cleaning with wire brush, sand paper, chemicals, providing & erecting necessary scaffolding to access all height with all safety precautions using PPE like safety belt, safety helmet, etc. complete as directed. (Approximate Height 35 mtr.)	Sqmt	1000.00		
2	Providing and applying exterior grade acrylic paint on walls, ceilings, beams etc. at all heights with two or more coats of Approved make & shade (e. g. Berger, Nerolac, Asian etc.) Including surface preparation like scraping & rubbing the old loose paint, laying the plastic sheet, filling the patches by plaster of Paris & white cement to make the surface even, all tools & tackles, ladders, wire rope etc. All the application work to be done by following the procedure specified by the manufacturer and explains practically during the execution of the work etc. complete as directed by engineer in charge.	Sqmt	300.00		
	Total Amount for B	Rs.			
	GST @ 18%	Rs.			
	Total Amount with GST for B	Rs.			l

M.c. Manda